

TLC for CLT

CITY OF CHARLOTTE

HOUSING & NEIGHBORHOOD SERVICES

Addendum 1 Invitation to Bid HNS 18-44

Documents included in Package:

- 1) Instruction to Bidders
- 2) Specs by Location/Trade (Scope of Work)
- 3) Subcontractor Certifications (if applicable)
- 4) Floor Plan / Site Drawing (if applicable)

Bid Walk & Bid Opening:

Project Addres	ss:			
2211 Highland St		Targeted Rehabilitation -		
2133 Highland St		Camp Greene Neighborhood		
Bid Walk: 3/1/18 at 9:00 am (THURSDAY) – 2211 Highland				
	3/1/18 at 10:00 am (THURSDAY) – 2133 Highland			
Bid Opening	Bid Opening: 3/8/18 at 2:00 pm (THURSDAY)			
Client Name: Angela James – 2211 Highland				
	Debra Neal – 2133 Highland			
Project Manag	er: Elizabeth Lamy	Contact Number: 704-620-9090		

Bid Walk and Bidding Instructions:

All bid walks are mandatory.

If you are going to be late the policy is the following:

Contact me BEFORE the start time if you are going to be late. If you are going to be more than 10 minutes late, we will proceed without you and you will not be permitted to bid.

The day of a bid walk the best way to reach me is at <u>Elizabeth Lamy</u> (cell # 704-620-9090). Bids must be received by the date, time and place specified. All others will be considered non responsive and disqualified.

The Bids will be opened at 600 East Trade St. immediately following the above due date and time.



TLC for CLT

CITY OF CHARLOTTE

HOUSING & NEIGHBORHOOD SERVICES

Company Acknowledgement:

The undersigned, having become thoroughly familiar with the terms, conditions, limitations, and provisions of the housing improvement work to be performed at 2211 Highland St and 2133 Highland St to be funded through the City of Charlotte Housing & Neighborhood Services, in addition, having fully inspected the site in all particulars, hereby proposes and agrees to fully perform the work within the time stated and in strict accordance with the proposed contract documents including furnishing of any and all labor and materials, and to do all work required to complete said Work in accordance with the advised respective contractual, for the sum of money:

including furnishing of any and all	labor and materials, and	l to do all v	work required to comple	te said
Work in accordance with the advi	sed respective contractu	ual, for th	e sum of money:	
All labor, materials, services a	nd equipment necessa	ry for the	completion of the Wo	ork shown
on the Drawings and in the Sp	ecifications:			
			Dollars (\$)
Written total				
Specs Dated:	Number of Pages:			
Addenda # 1 Dated: 3 5/18	Number of Pages:	29	US	
Addenda # 2 Dated:	Number of Pages:		1.0000	
Project Schedule: Minimum Start	: Date - upon issuance of	f NTP	Marie	
Completion Deadline: (please pr	ovide projected complet	tion date v	vith bid submission)	
Please Print and Sign:				
Company Name/Firm:				
Authorized Representative Name				
Signature:		Date:		



TLC for CLT

CITY OF CHARLOTTE

HOUSING & NEIGHBORHOOD SERVICES

Requirements For Bidders

The City awards rehabilitation bids to the lowest responsive and responsible bidder. A responsible bidder for the safe home program is one who:

- 1) Is a licensed general contractor in the State of North Carolina;
- 2) Has an Renovate, Repair & Paint Certification (http://www2.epa.gov/lead/renovation-repair-and-painting-program);
- 3) Is not listed on a local, state or federal debarment list;
- 4) Carries an appropriate amounts of insurance;
- 5) Can provide references verifying the contractor has completed work of a similar scope in a good workmanship like manner or successfully completed prior work for the Safe Home program. Referenced work must have been completed in one year or less from date of this invitation to bid.

A responsive bidder must:

- 1) Submit all requested documentation on time;
- 2) Meet the above requirements for responsibility at the time of bid submittal;
- 3) Have the capacity to meet the required schedule for the project.
- 4) Existing rehab projects contracted by the contractor must be on schedule.

The City reserves the right to waive any minor informalities or irregularities, which do not go to the heart of the bid submittal or prejudice other offers, or to reject, for good and compelling reasons, any or all bid submittals.

Elizabeth Lamy Santos
Rehabilitation Specialist
City of Charlotte
Housing and Neighborhood Services
600 E. Trade St.
Charlotte, NC 29202

PH: (704) 336-3333 Cell: (704) 620-9090

HOUSING & NEIGHBORHOOD SERVICES

http://housing.charlottenc.gov | 600 E. Trade Street | Charlotte, NC

Property Details

Prepared By:
City of Charlotte Housing & Neighborhood Services
600 E. Trade Street
Charlotte, NC 28202
(704) 336-7600

Address:	2211 Highland St Charlotte, NC 28208	Owner:	Angela James
		Owner Phone:	Home: (704) 649-1086
Structure Type:	Single Unit	Program(s):	Targeted Rehab Program (C1)
Square Feet:	1200		LeadSafe 2016 Healthy Homes LBP 2016
Year Built:	1938		, , , , , , , , , , , , , , , , , , ,
Property Value:	85300		
Tax Parcel:	06706302		
Census Tract:			
Property Zone:	Council District 3		

Fiberglass Bathtub and Shower Surround

BATHROOM - MAIN

Install a 5' white Swan or equivalent 3-piece, fiberglass bathtub and surround. Caulk all seams and penetrations. Include new single handled tub/shower diverter valve and drain.



Bid Cost: _		X	
_	Base	Quantity	Total Cost

17" Height Commode Replace

BATHROOM - MAIN

Install a 17" height, 2 piece, close coupled, white, vitreous china commode with a maximum water usage per flush of 1.6 gallons. Include plastic or pressed wood white seat, supply pipe, shut-off valve, flap valve and wax seal.

Bid Cost:	2	x=_	
	Base	Quantity	Total Cost

Pedestal Sink - Complete

BATHROOM - MAIN

Install a vitreous china pedestal lavatory complete with single handled metal faucet with drain and pop-up, p-trap, supply lines, full port ball type shut-off valves & escutcheon plates. All materials and work shall comply with the Construction Standards and the Plumbing Code.

	Bid Cost:	x	=	
		Base	Quantity	Total Cost
Floor System Repair			BATHROOM	- MAIN
Remove all fixtures not built in. Dispose of floor assembly. all deteriorated band joists and insulating floor to code.	Install 2"x 10" jois	ts hung 16" on	center, 3/4" subfloc	or. Include replacing
	Bid Cost:	x	=	
		Base	Quantity	Total Cost
Prep & Paint Room Semi Gloss			BATHROOM	- MAIN
Remove or cover hardware and accessories not to be paint fungus, dirt, and dust from surfaces. Fill holes and cracks. Fill holes and crac	Prime all new mate . Painting shall inc	rials and spot p lude walls and	orime existing with a	acrylic latex. Top coat
	Bid Cost:	x		
		Base	Quantity	Total Cost
Prep & Paint Ceiling			BATHROOM	- MAIN
Remove or cover hardware and accessories not to be paint fungus, dirt, and dust from surfaces. Fill holes and cracks. I with Owner's choice of low VOC acrylic flat latex in all habit Replace or uncover hardware, fixtures and accessories. An	Prime all new mate able rooms and lo	rials and spot p w VOC acrylic s	orime existing with a semi-gloss latex in l	acrylic latex. Top coat
	Bid Cost:	x	==	

Base

Quantity

Total Cost

Resilient Flooring

BATHROOM - MAIN

Install 25 year warrantied resilient floor covering per manufacturer's specifications. Include transitions and painted or stained wood quarter-round at all perimeters to complete installation.

- Andrew Company of the Company of t
L TRIME AND A CO. A.

Bid Cost:	X=			
	Base	Quantity	Total Cost	

Grab Bars

BATHROOM - MAIN


Install 1 1/2" diameter S/S Grab Bars on 3 walls at height of 36" (include wood blocking in wall. Each bar must hold 300 pounds). Owners choice of locations. (38.1)


Bid Cost: _	×	=		
	Base	Quantity	Total Cost	

Bath Exhaust Fan Replace

BATHROOM - MAIN

Install a ceiling or through-the-wall, exterior ducted, vent fan with damper. Include power and switch wiring using #14 copper Romex. Repair any tear out.





Light Fixture Replace

BEDROOM

Replace or install a ceiling mounted 2 bulb or wall mounted 4 bulb strip, UL approved, CFL or LED light fixture with shade and lamps.



Bid Cost:		X	
	Base	Quantity	Total Cost

Light Fixture Replace

BEDROOM 2

Replace or install a ceiling mounted 2 bulb or wall mounted 4 bulb strip, UL approved, CFL or LED light fixture with shade and lamps.



Bid Cost: _		X=	
	Base	Quantity	Total Cost

Work opecification				
Light Fixture Replace			BEDROOM 3	
Replace or install a ceiling mounted 2 bulb or wal	l mounted 4 bulb strip, UL ap	proved, CFL o	r LED light fixture wit	h shade and lamps.
	Bid Cost:	x	=	
	<u></u>	Base	Quantity	Total Cost
1 to				
Remove and Dispose of Exterior Deck			EXTERIOR	Exterior
Demolish and dispose of existing exterior deck, in	cluding railings and steps.			
	Bid Cost:	x	=	
		Base	Quantity	Total Cost
Exterior Deck Replacement			EXTERIOR	Exterior
Construct a new deck and set of steps serving the Dimensions of new deck are to be smaller than exhauld be constructed of treated lumber and in accordance.	kisting deck - around 10' x 10)'. Deck and ra	illings, as well as nev	
	Bid Cost:	x	==	
		Base	Quantity	
Vinyl Siding - Repair			EXTERIOR	Exterior
Repair/re-secure loose vinyl siding.				
	Bid Cost:		=	T-4-1 04
		Base	Quantity	Total Cost

Crawl Space Access Door			EXTE	ERIOR	Exterior
Install a 3/4" pressure treated plywood access door in a 2"	x 4" pressure treat	ed frame. Pr	ovide galvani	zed iron hi	nges and hasp.
	Bid Cost:		X	=	
三		Base	Quant	ity	Total Cost
Prehung Metal Door Entrance - Rear Entry			EXTE	RIOR	Exterior
Remove existing door, frame and threshold. Install new Endead bolt and lever handled door hardware keyed alike. Instally primer and topcoat, this installation to include repairing floor joists and sill.	stall wide peep sigl	nt. New casin	g and shoe m	olding will	match existing.
	Bid Cost:		x	=	
		Base	Quant	ity	Total Cost
Aluminum Fascia			EXTE	RIOR	Exterior
Wrap all fascia and wood trim with PVC coated aluminum of ***Fascia is to be repaired at the rear of the home, at the la		n ONLY.			
	Bid Cost:		X	=	
	Bid Cost	Base	Quant	ity	Total Cost
Masonry Patch & Repoint			EXTE	RIOR	Exterior
Install bricks where missing. Cut out mortar at least 1/2". R repoint in 1/2" lifts using portland cement mortar. Reinstall					ts with water and
	Bid Cost:		x	=	
	Biu Cost	Base	Quant	ity	Total Cost

A001

Work Specification

Custom Awning Repair and Repaint			EXTERIOR	Exterior
Repair damaged metal awning above windows and front pe	orch and repaint al	awnings.		
	Bid Cost:		X=_	
		Base	Quantity	Total Cost
Dryer Vent			EXTERIOR	Exterior
Install 4" rigid aluminum vent tubing from the specified drye and NO screening. Fasteners shall not protrude into the in or aluminum foil tape, not duct tape. Secure duct and hood	nterior of the exhau			
	Bid Cost:		X=	
		Base	Quantity	Total Cost
Combination CO / Smoke Detector Hard Wired			GENERAL RE	QUIREMENTS
				~ 0
Install a hard wired combination carbon monoxide and smo	oke detector with b	attery back up	•	
Install a hard wired combination carbon monoxide and smo			X =	
Install a hard wired combination carbon monoxide and smo	oke detector with ba			Total Cost
Install a hard wired combination carbon monoxide and smo			X=_	Total Cost
	Bid Cost: te and heat detectors.	Base rs permanenti	X = Quantity GENERAL REG y wired into a receptace	Total Cost QUIREMENTS cle boxes with
Smoke Detector Hard Wired Install UL approved, interconnected, ceiling mounted smok battery backups in bedrooms and outside of sleeping areas	Bid Cost: te and heat detectors. actor responsible to	Base rs permanent field verify du	X = Quantity GENERAL REG y wired into a receptace	Total Cost QUIREMENTS cle boxes with
Smoke Detector Hard Wired Install UL approved, interconnected, ceiling mounted smok battery backups in bedrooms and outside of sleeping areas	Bid Cost: te and heat detectors.	Base rs permanent field verify du	Quantity GENERAL REC y wired into a receptace e to additions to the ho	Total Cost QUIREMENTS cle boxes with
Smoke Detector Hard Wired Install UL approved, interconnected, ceiling mounted smok battery backups in bedrooms and outside of sleeping areas	Bid Cost: te and heat detectors. actor responsible to	Base rs permanenti	Quantity GENERAL REC y wired into a receptace e to additions to the ho	Total Cost QUIREMENTS cle boxes with ome. Total Cost

Bid Cost: ___

Base

Total Cost

Quantity

Electric Service 200 AMP

GENERAL REQUIREMENTS

Replace electrical service with new 200 amp, main disconnect, 110/220 volt, 24 circuit panel board, meter socket, weather head, service cable, ground rods and cable. Include replacement of all sub-panels. Caulk exterior service penetration.

2	

Bid Cost: _	x		
	Base	Quantity	Total Cost

Floor System Repair - Allowance (Living Room Area)

GENERAL REQUIREMENTS

Remove all fixtures not built in. Dispose of floor assembly. Install 2"x 10" joists hung 16" on center, 3/4" subfloor. Include replacing all deteriorated band joists and insulating floor to code.

	Bid Cost:	x	=_	
		Base	Quantity	Total Cost
Portable Toilet			GENERAL R	EQUIREMENTS
Provide temporary toilet facilities from job start until approva	l of permanent fa	cilities.		
	Bid Cost:	x	<u> </u>	
		Base	Quantity	Total Cost
Permits Required			GENERAL R	EQUIREMENTS
The contractor is responsible obtaining and paying for all pe	rmits required, Sa	iid permits shal	I include all items in	this scope of work.
	Bid Cost:	x	=_	
		Base	Quantity	Total Cost
See Attached Lead Scope			GENERAL R	EQUIREMENTS
See Attached Lead Scope All work shall be performed in accordance with applicable re will be obtained as appropriate. Mecklenburg County require activities subject to permitting under general conducts.			icable building code	es. Building permits
All work shall be performed in accordance with applicable re will be obtained as appropriate. Mecklenburg County require		s for Lead Haza	icable building codord Reduction if the	es. Building permits

House Number

GENERAL REQUIREMENTS

Install brass, aluminum, or iron house numbers with nails. Numbers must be 4 inches tall with a stroke-width of 1/2 inch per Code. Numbers are not permitted to be plastic or stickers.

Numbers are not permitted to be plastic or su	ionora.			
	Bid Cost:	Base	Quantity	Total Cost
Dumpster			GENERAL R	EQUIREMENTS
After procuring all required permits, place AS debris using dust control methods. Remove caway daily using dump trailers.				
	Bid Cost:)	<=_	
		Base	Quantity	Total Cost
Exterminate Termites	en versigen in der eine ver			EQUIREMENTS
Exterminate for termites. Drill and patch foun rear guarantee with an optional yearly renew			inator must be licen	sed and provide a
	Bid Cost:)	(=	
		Base	Quantity	Total Cost
Replumb Supply Lines			GENERAL R	EQUIREMENTS
Remove all existing water supply lines. Instal nsulate exposed hot and cold water lines, in				
	Bid Cost: _		(<u> </u>	
		Base	Quantity	Total Cost

Replumb Waste Lines & Vents

GENERAL REQUIREMENTS

Remove all drain, waste and wet vent lines to code legal dump. Install schedule 40 PVC to service one 3-piece bath, kitchen and laundry area from the roof vent pipe/pipes thru the foundation wall to include a main clean out outside of house and any interior clean outs required, installed to code. Repair any wall or ceiling tear out required to install system.

The second secon
Strattle manufacture
J. 7

Bid Cost:	x		=		x=	
	Base		Quantity	Total Cost		

Floor System Repair - Allowance (Kitchen Area)

KITCHEN

Remove all fixtures not built in. Dispose of damaged/unsafe components of floor assembly. Work may include installation of 2"x 10" joists hung 16" on center, plywood or tongue and groove subfloor. Include replacing all deteriorated band joists and insulating floor to

***Crawlspace was inaccessible due to presence of sewage. Allowance here is for any floor structure repair necessary along the kitchen/laundry room band area.

Bid Cost:		X=_		
	Base	Quantity	Total Cost	
		KITCHEN		

Counter Tops Replace

Screw to base cabinet a square edged plastic laminate counter top. Provide end-caps and cutout for sink. Caulk counter top to adjoining walls with low VOC caulking to match wall color. Owner's choice of in-stock color and texture.



Bid Cost:	x		
	Base	Quantity	Total Cost

Cabinets Base

KITCHEN

Replace base cabinets. Cabinets to be constructed of solid maple and plywood. No particle board allowed. See contractor's manual guidelines & specifications for full requirements.

*Select unfinished base cabinets and stain to match existing wall cabinets a best as possible.



Bid Cost:	X		
	Base	Quantity	Total Cost

A00 1

Work Specification

Double Bowl Sink Complete

KITCHEN

Install a 18 gauge 33" x 22" x 9" double bowl, stainless steel, self rimming kitchen sink including a single handle metal body faucet, rated at 2.0 GPM or less, with a 15 year drip- free warranty, P-trap, supply lines, full port ball type shut-off valves & escutcheon plates on all supply & drain lines. No copper compression fittings.

- In	
A	
	-
ant control of the co	
A.	

Bid Cost: _	,	X=_	
	Base	Quantity	Total Cost

Masonry Pier and Curtain Foundation Wall and Pier Replacement

LAUNDRY

Construct a masonry pier and curtain wall with concrete footings for the laundry room/bedroom extension addition.

Also,replace existing piers under the laundry room floor system with new masonry piers with mortared joints and poured concrete footing per Code.



Bid Cost: _		X=	
	Base	Quantity	Total Cost

Water Heater 40 Gallon Electric

LAUNDRY

Install a 40 gallon, glass lined, high recovery insulated to R-7, double element, electric water heater with 10 year warranty. Include pressure and temperature relief valve, expansion tank, discharge tube to within 6" of floor or to outside of structure, shut-off valve and electric supply. If it is located on an upper floor or if there is no floor drain, install a catch pan drained to the exterior. Dispose of old water heater appropriately.



Bid Cost:		x=	
	Base	Quantity	Total Cost

Wall Finish Repair and Repaint

LIVING ROOM

Quantity

Total Cost

Repair wall finish. Patch drywall or plaster holes in wall greater than one inch. All others use an adhesive mesh and mud over the mesh with the appropriate material. Wet sand smooth. Repaint repaired area to match existing.

***Price here also include repair/repainting of baseboard trim as well.

Base

			·	
Gas Furnace Replacement			UTILITY	
Install a gas fired, forced air furnace with minimum ignition. Include programmable thermostat, flue pip Manual J calculations. Dispose of old furnace appropriate the control of the cont	e and shut- off valve. Size			
	Bid Cost:)	(: =	
	_	Base	Quantity	Total Cost
Bi-Fold/Sliding Door			UTILITY	
Bi-Fold/Sliding Door Close up existing access door to the furnace close frame and hang a hollow core, bi-fold or sliding doo the opening.			ne deeper wall of clo	
Close up existing access door to the furnace close frame and hang a hollow core, bi-fold or sliding doo	or, including appropriate tra	acks, all hardw	ne deeper wall of clo	
Close up existing access door to the furnace close frame and hang a hollow core, bi-fold or sliding doo	or, including appropriate tra	acks, all hardw	ne deeper wall of closers and casing, plum	
Close up existing access door to the furnace close frame and hang a hollow core, bi-fold or sliding doo	or, including appropriate tra	acks, all hardw	ne deeper wall of closers and casing, plum	b and centered within
Close up existing access door to the furnace close frame and hang a hollow core, bi-fold or sliding doo the opening.	or, including appropriate tra	acks, all hardw	ne deeper wall of closers and casing, plum	b and centered within



LEAD ABATEMENT SCOPE OF WORK & INSTRUCTIONS TO BIDDERS

Address

Ite

23-Jan-18 2211 Highland St

Complete the following scope of work:

#	Feature	Method	Number	Cost Per unit	COST
1	wells (many of the aluminum coverings are partially detached and many wood components rotted) EXCEPT	Replace windows (all components) with vinyl replacement windows and cover with Tyvek and aluminum. ***Price to include any necessary replacement of rotten window framing.	16		
2	Side A and Side D Porch - white wood ceiling support beams (under the metal awnings)	Cover with Tyvek and aluminum.	1		
	J. J	Scrape loose paint and re-paint on all concrete	2		
	Room 1 - Screen Porch - Side A, Side D and Ceiling - white wood ceiling, crown moldings, ceiling support beams and trim boards	Scrape loose paint and re-paint.	1		
	sills and white wood sashes and wells (wood components	Replace wood sashes and wells with vinyl replacement windows, and remove aluminum window coverings and cover window casings, headers and sills with Tyvek and aluminum.	2		
	Room 9 - Mud Room - Door A1 - white wood door jambs and stops (door DOES NOT contain lead, but is damaged and entire door will be replaced.)	Replace entire door with prehung door.	1		
7	Elevated Dust Levels on Room 2 Floor and Windowsills	Complete specialized cleaning.	1		

Total

Contractors may submit an occupant protection plan on the form provided.

Complete all interior work in a unit in a single day.

NOTES: Allow for replacement of 50 board feet of rotted wood.

- 1 Unless otherwise noted any window or door removal and replacement
- 2 includes frame and trim on both sides.
- 3 In lieu of complete removal, window frames may be enclosed with vinyl on.
- 4 Exterior in accordance with all project manual requirements
- 5 Contact Jim Roy to conduct inspections prior to repainting or other putback and
- 6 after vinyl siding installation.

Windows being placed in a bathroom need to be tempered glass.

, Te

Total Bid

Acknowledgement of Addenda (if any):

Addendum#	Date

The undersigned contractor agrees to perform the scope of work for the indicated fee in accordance with applicable regulations and the project manual. The undersigned also certifies that the work will be completed within 60 days of award.

Signature of authorized contractor representative

Contractor Submitting Bid:

Address:

Phone:


SIDE B

ROY CONSULTING GROUP CORPORATION

2211 Highland Street

Providing integrated environmental and geotechnical solutions

Charlotte, NC 28208



Legend

= Window

= Soil Sample Location = Door

SIDE A

NOT TO SCALE

SIDE D

Prepared By:
City of Charlotte Housing & Neighborhood Services
600 E. Trade Street
Charlotte, NC 28202
(704) 336-7600

Property Details		n (aprila de 1986). Se internación de 1986		Gloades I - 1935 Globales I - 1986		
Address:	2133 Highland S	t	Owne	er:	Debra Neal	
	Charlotte, NC 28	208	Own	er Phone:	Cell: (704) 408-2	552
Structure Type:	Single Unit		Prog	ram(s):	Targeted Rehab	Program (C1)
Square Feet:	1218					
Year Built:	1941					
Property Value:	74000					
Tax Parcel:	06706707					
Census Tract:						
Property Zone:	Council District 3	3				
Folding Attic Stairs					ATTIC	
Replace utility folding sta	airway, after doubl	ling framing at ceiling. In:	stall casing to	match tri	m in room.	
		Ri	d Cost:		X	=
				Base	Quantity	Total Cost
Drywall Entire Room					BATHRO	OM - HALF
Remove all gypsum, pan code. Glue, nail and screpaint.						ulation as required by finish. Wet sand ready for
		Ві	d Cost:		х	=

Prep & Paint Room Semi Gloss

BATHROOM - HALF

Remove or cover hardware and accessories not to be painted. Scrape loose, peeling, cracked and blistered areas. Clean oil, grease, fungus, dirt, and dust from surfaces. Fill holes and cracks. Prime all new materials and spot prime existing with acrylic latex. Top coat with owner's choice of low VOC acrylic SEMI-GLOSS latex. Painting shall include walls and any associated trim. Replace or uncover hardware, fixtures and accessories. Any moving of furniture required shall be included.

	Bid Cost:	X Base	=_ Quantity	Total Cost
Light Fixture Replace			BATHROOM	- HALF
Replace or install a ceiling mounted 2 bulb or wall mounted 4	bulb strip, UL a	oproved, CFL or	LED light fixture wi	th shade and lamps.
	Bid Cost:	x	=	
		Base	Quantity	Total Cost
Fiberglass Walk-In Shower - Pan ONLY			BATHROOM	- MAIN
Install Mustee or equivalent fiberglass shower pan unit equiv			te with single lever	shower diverter,
shower rod and water saving shower head. Caulk all seams	and periodiations) ,		
shower rod and water saving shower flead. Caulk all sealins			. =	
shower rod and water saving shower flead. Caulk all sealins	Bid Cost:		=	Total Cost
Shower rod and water saving shower flead. Caulk all sealins Ceramic Wall Tile		x		
	Bid Cost: d with troweled a s drying time, ap	Base Idhesive. Includ	Quantity BATHROOM e preformed base, portland cement gro	- MAIN cap, stop, return and

Base

Quantity

Total Cost

Add 1

Work Specification

17" Height Commode Replace

BATHROOM - MAIN

Install a 17" height, 2 piece, close coupled, white, vitreous china commode with a maximum water usage per flush of 1.6 gallons. Include plastic or pressed wood white seat, supply pipe, shut-off valve, flap valve and wax seal.

The state of the second
The second secon
4 30 1/40
TO AND THE PROPERTY OF THE PRO

Bid Cost:		X=	
	Base	Quantity	Total Cost

Bath Exhaust Fan - New Installation

BATHROOM - MAIN

Install a ceiling or through-the-wall, exterior ducted, vent fan with damper. Include power and switch wiring using #14 copper Romex. Repair any tear out.



Bid Cost: _		_x	=
	Base	Quantity	Total Cost

Prep & Paint Room Semi Gloss

BATHROOM - MAIN

Remove or cover hardware and accessories not to be painted. Scrape loose, peeling, cracked and blistered areas. Clean oil, grease, fungus, dirt, and dust from surfaces. Fill holes and cracks. Prime all new materials and spot prime existing with acrylic latex. Top coat with owner's choice of low VOC acrylic SEMI-GLOSS latex. Painting shall include walls and any associated trim. Replace or uncover hardware, fixtures and accessories. Any moving of furniture required shall be included.



Bid Cost:	>	<=_	
,	Base	Quantity	Total Cost

Prep & Paint Ceiling

BATHROOM - MAIN

Remove or cover hardware and accessories not to be painted. Scrape loose, peeling, cracked, and blistered areas. Clean oil, grease, fungus, dirt, and dust from surfaces. Fill holes and cracks. Prime all new materials and spot prime existing with acrylic latex. Top coat with Owner's choice of low VOC acrylic flat latex in all habitable rooms and low VOC acrylic semi-gloss latex in kitchen and baths. Replace or uncover hardware, fixtures and accessories. Any moving of furniture required shall be included.



Bid Cost:	X =			
	Base	Quantity	Total Cost	

Resilient Flooring	DEN
Install 25 year warrantied resilient floor covering per manufacturer's	s specifications. Include transitions and painted or stained wood
quarter-round at all perimeters to complete installation.	



Bid Cost:		X=	
	Base	Quantity	Total Cost

Exterior Steps Replace

EXTERIOR

Exterior

Replace existing wood steps and stringers to Code. New treads shall be two 2" x 6" spaced 1/2" apart, and have 2" 12" stringers. Wooden handrails should include pickets installed to Code. Entire stair system should be constructed using pressure-treated lumber. New steps and handrails are to be painted white.



Bid Cost: _	X	=	=	
	Base	Quantity	Total Cost	

Seamless Aluminum Gutter & Downspouts - Install

EXTERIOR

Exterior

Install K- type .027 gauge seamless aluminum gutter to service roof with sufficient pitch to downspouts. White or brown color choice by owner.



Bid Cost: _____ = _____ Base Quantity Total Cost

Crawl Space Access Door

EXTERIOR

Exterior

Install a 3/4" pressure treated plywood access door in a 2" x 4" pressure treated frame. Provide galvanized iron hinges and hasp.



Bid Cost:		X=	
	Base	Quantity	Total Cost

Aluminum Storm Door - Rear Entry				EXTERIOR	Exterior
Install an aluminum combination storm and screen door. Comp	lete with self cl	oser and loc	king h	ardware.	
	Bid Cost:		_x	=_	***************************************
		Base		Quantity	Total Cost
Vinyl Siding - Repair				EXTERIOR	Exterior
Trim pieces of corner trim/J-channel/any other associated white	e vinyl trim on t	he exterior tl	hat ma	y be too long.	
	Bid Cost:		_x	=_	
		Base		Quantity	Total Cost
Vinyl Siding - Window Trim Repair				EXTERIOR	Exterior
Replace damaged piece of trim above window at the rear of the	e home.				
	Bid Cost:		_x	=	
24		Base		Quantity	Total Cost
Vinyl Siding - Repair				EXTERIOR	Exterior
Repair/replace damaged vinyl siding along right bottom wall of	home.				
	Bid Cost:		_x	=_	
Part of the second seco		Base		Quantity	Total Cost

tod 1

Work Specification

Exterior Handrails - Left Front Entry

EXTERIOR

Exterior

Remove existing handrails. Dispose of properly. Re-install handrails to current building code- specified treated lumber, painted white. Ensure that new handrail matches new handrails installed at main front entry. Size & dimensions to code.



Bid Cost:		X	=	
	Base	Quantity	Total Cost	

Aluminum Storm Door - Left Front Entry

EXTERIOR

Exterior

Install an aluminum combination storm and screen door. Complete with self closer and locking hardware.



Bid Cost: _	X_	=	=	
	Base	Quantity	Total Cost	

Water Heater 40 Gallon Electric

GENERAL REQUIREMENTS

Install a 40 gallon, glass lined, high recovery insulated to R-7, double element, electric water heater with 10 year warranty. Include pressure and temperature relief valve, expansion tank, discharge tube to within 6" of floor or to outside of structure, shut-off valve and electric supply. If it is located on an upper floor or if there is no floor drain, install a catch pan drained to the exterior. Dispose of old water heater appropriately.



Bid Cost: _	>	` <u> </u>		
	Base	Quantity	Total Cost	

Heat Pump Replace

GENERAL REQUIREMENTS

Install an Energy Star rated 14 SEER or higher heat pump compatible with the indoor unit. Support unit on a level concrete pad with a minimum of 3' clearance around coil. Reinsulates bare areas of refrigerant piping. Properly dispose of existing unit.

***Please remove existing gas pack and convert to all electric.



Bid Cost:		X	=	
	Base	Quantity	Total Cost	

Add 1

Work Specification

Portable Toilet			GENERAL	REQUIREMENTS
Provide temporary toilet facilities from job start until approva	of permanent fa	cilities.		
	Rid Cost:)	×=	
	Did Cost	Base	Quantity	Total Cost
Permits Required			GENERAL	REQUIREMENTS
he contractor is responsible obtaining and paying for all per	mits required. Sa	aid permits sha	Il include all items	in this scope of work
	Pid Coats	,	· =	
	Bid Cost:	Base	X= Quantity	Total Cost
See Attached Lead Scope				REQUIREMENTS
•	mulations	- II II -		·
All work shall be performed in accordance with applicable re- vill be obtained as appropriate. Mecklenburg County require activities subject to permitting under general conducts.	-	, ,	_	
	Bid Cost: _		<=	
		Base	Quantity	Total Cost
Dumpster			GENERAL I	REQUIREMENTS
After procuring all required permits, place AS MANY roll-off of debris using dust control methods. Remove dumpster and reaway daily using dump trailers.	•			
	Bid Cost:)	<=	
		Base	Quantity	Total Cost
Combination CO / Smoke Detector Hard Wired			GENERAL	REQUIREMENTS
nstall a hard wired combination carbon monoxide and smok	e detector with b	attery back up.		
	Bid Cost:	,	(=	
	Did Cost	Base	Quantity	Total Cost
Smoke Detector Hard Wired			GENERAL I	REQUIREMENTS
nstall UL approved, interconnected, ceiling mounted smoke pattery backups in bedrooms and outside of sleeping areas.	and heat detecto	ors permanently	y wired into a recep	tacle boxes with
	Bid Cost:)	(=	
		Base	Quantity	Total Cost
			-	

Electric Service 200 AMP

GENERAL REQUIREMENTS

Replace electrical service with new 200 amp, main disconnect, 110/220 volt, 24 circuit panel board, meter socket, weather head, service cable, ground rods and cable. Include replacement of all sub-panels. Caulk exterior service penetration.

	decimanded and the second and the se	And the second of the second o
	200	,882

Bid Cost:		X	=
	Base	Quantity	Total Cost

Dryer Vent

GENERAL REQUIREMENTS

Install 4" rigid aluminum vent tubing from the specified dryer location to a 4" wall mounted dryer vent hood with a back flow preventer and NO screening. Fasteners shall not protrude into the interior of the exhaust duct. Seal all seams in the system with duct mastic or aluminum foil tape, not duct tape. Secure duct and hood to framing.



Bid Cost: _		X=	
	Base	Quantity	Total Cost

Replace Receptacles, Switches, and Plates

GENERAL REQUIREMENTS

Replace all receptacles, switches and cover plates throughout entire house. Use code appropriate devices. This includes any new wire required to install GFCI's in kitchen and bathrooms. This also includes any wall or ceiling damage repairs.

	Bid Cost: _		x_		
		Base		Quantity	Total Cost
the same graphs and the same states and the same states are same state					

Replace/Install Duct Work System

GENERAL REQUIREMENTS

Replace all ductwork and supply mixing box plenum. Ensure system is properly supported from ground (supply, return, and flex.) Ductwork shall be R-8 and mastic sealed.

Bid Cost: X = Base Quantity Total Cost

Resilient Flooring

HALL

Install 25 year warrantied resilient floor covering per manufacturer's specifications. Include transitions and painted or stained wood quarter-round at all perimeters to complete installation.



Bid Cost:)	(:	=
	Base	Quantity	Total Cost

Wall Finish Repair and Repaint

HALL

Repair wall finish to match as close as possible as wall is currently painted wood paneling. Patch holes in wall greater than one inch. Repaint area to match existing.



Bid Cost: _		X=	=
	Base	Quantity	Total Cost

Cabinets Wall

KITCHEN

Replace wall cabinets. Cabinets are to be constructed of solid maple and plywood. No particle board allowed. See contractor's manual guidelines & specifications for full requirements.

***Selection should be made to best match existing base cabinets, possibly including selecting unfinished cabinets and staining to match.



Bid Cost: X = Total Cost

Range Hood Exterior Vented

KITCHEN

Install an exterior ducted enameled range hood with integral controls and light capable of 100 cfm at 70 sones. Attach hood to cabinet with screws. Include metal vent and roof or wall cap/damper assembly, using #14 copper Romex. Owner's choice of color.



Bid Cost:		_x	=
	Base	Quantity	Total Cost

Prep & Paint Room Semi Gloss

KITCHEN

Remove or cover hardware and accessories not to be painted. Scrape loose, peeling, cracked and blistered areas. Clean oil, grease, fungus, dirt, and dust from surfaces. Fill holes and cracks. Prime all new materials and spot prime existing with acrylic latex. Top coat with owner's choice of low VOC acrylic SEMI-GLOSS latex. Painting shall include walls and any associated trim. Replace or uncover hardware, fixtures and accessories. Any moving of furniture required shall be included.

***Include in this work proper finishing techniques to remove excess spray foam above kitchen sink area.

A	
通 力	
100	
	Military
the second secon	

Bid Cost:		X=_		
	Base	Quantity	Total Cost	

Resilient Flooring

LAUNDRY / UTILITY

Install 25 year warrantied resilient floor covering per manufacturer's specifications. Include transitions and painted or stained wood quarter-round at all perimeters to complete installation.



Bid Cost:		X=_	
	Base	Quantity	Total Cost

Light Fixture Replace

LAUNDRY / UTILITY

Replace or install a ceiling mounted 2 bulb or wall mounted 4 bulb strip, UL approved, CFL or LED light fixture with shade and lamps.



Bid Cost:		X=	
	Base	Quantity	Total Cost

Prehung Metal Door - Laundry Room

LAUNDRY / UTILITY

Remove existing door, frame and threshold. Install new Energy Star rated pre-hung exterior door. Insulate cavity. Install mortised dead bolt and lever handled door hardware keyed alike. Install wide peep sight. New casing and shoe molding will match existing. Apply primer and topcoat, this installation to include repairing any damaged header, door framing, to include wall framing, sub-floor, floor joists and sill.



Bid Cost: _		X=	
	Base	Quantity	Total Cost

X00 1

Work Specification

Prep & Paint Ceiling

LIVING ROOM

Remove or cover hardware and accessories not to be painted. Scrape loose, peeling, cracked, and blistered areas. Clean oil, grease, fungus, dirt, and dust from surfaces. Fill holes and cracks. Prime all new materials and spot prime existing with acrylic latex. Top coat with Owner's choice of low VOC acrylic flat latex in all habitable rooms and low VOC acrylic semi-gloss latex in kitchen and baths. Replace or uncover hardware, fixtures and accessories. Any moving of furniture required shall be included.

	Bid Cost:		X=_	
		Base	Quantity	Total Cost
Prep & Paint Room Flat			LIVING ROO	М
Remove or cover hardware and accessories not to be painted fungus, dirt, and dust from surfaces. Fill holes and cracks. Pwith owner's choice of low VOC acrylic FLAT latex. Painting Replace or uncover hardware, fixtures and accessories. Any ***Painting trim includes painting all window trim.	rime all new mate shall include wal	erials and spot s and any ass	prime existing with a cociated trim with SEI	acrylic latex. Top coat
	Bid Cost:		x=_	
		Base	Quantity	Total Cost
Certification				
Contractor Name:			Total Cost:	
Signature:			Date:	

166A

LEAD ABATEMENT SCOPE OF WORK

& INSTRUCTIONS TO BIDDERS

23-Jan-18

Address

Complete the following scope of work:

2133 Highland St

n #	Feature	Method	Number	Cost Per unit	COST
	Room 2 - Mud Room - Ceiling - EXPOSED, light brown wainscot ceiling (partially exposed and exists above ceiling tile/wallboard)	Remove wainscot ceiling and replace with wallboard or wood panel. ***Price includes removal of all existing ceiling finish materials and replacing with wallboard, prep and painting.	1		
	Room 2 - Mud Room - Door D1 - white wood door casings and header (no door)	Replace.	1		
	Room 3 - Bath 1 - Window B1 - white wood window casings, header, apron and sill	Replace.	1		
	Room 9 - Laundry Room - Door B1 - white and light brown wood door jambs (no door and no stops)	Replace.	1		
5	Elevated Dust Levels on Floor - Room 9	Complete specialized cleaning.	1		;

Total

Contractors may submit an occupant protection plan on the form provided.

Complete all interior work in a unit in a single day.

NOTES: Allow for replacement of 50 board feet of rotted wood.

- 1 Unless otherwise noted any window or door removal and replacement
- 2 includes frame and trim on both sides.
- 3 In lieu of complete removal, window frames may be enclosed with vinyl on.
- 4 Exterior in accordance with all project manual requirements
- $5 \ \ Contact \ Jim \ Roy \ to \ conduct \ inspections \ prior \ to \ repainting \ or \ other \ putback \ and$
- 6 after vinyl siding installation.
 - Windows being placed in a bathroom need to be tempered glass.

/

Total Bid

Acknowledgement of Addenda (if any):

Addendum#	Date

The undersigned contractor agrees to perform the scope of work for the indicated fee in accordance with applicable regulations and the project manual. The undersigned also certifies that the work will be completed within 60 days of award.

Signature of authorized contractor representative

Contractor Submitting Bid:

Address:

Phone:

ROY CONSULTING GROUP CORPORATION

Providing integrated environmental and geotechnical solutions

2133 Highland Street Charlotte, NC 28208

SIDE C

F801 2133 Free3 ≪ ゃ Concrete

SIDE D

SIDE B

Legend

+ = Window

· = Door = Soil Sample Location

SIDE A

NOT TO SCALE